pda.org



Mastering AVI

Part 4: Selection and purchasing of an automated inspection system

- Technical requirements
- Integration into existing processes, lines/ machines and systems
- Cost and effort considerations
- Risk Assessment



Instructor Lead: Romain Veillon / Fernand Koert / Sébastien Koch





Where to start?

- When procurement of AVI machine is foreseen you may consider all these aspects:
- User Requirements, typically the URS document
- Engineering specifications
- EHS rules
- Contractual terms
 - Payment terms / conditions
 - Project mngt / key milestones
 - Target KPIs
 - Training
 - Key milestones (commisioning / validation / ramp up)
 - Performance based contract





2














Some challenges





Cost / Payback









Company culture

• What are Silos in your company ?



- Production
- Maintenance
- Engineering
- Procurement
- QA
- QC
- RA
- PMOs

. . . .

• EHS : Ergonomy

1 URS+1 Contract





pda.org





Topics to cover in URS

URS	Eng. Spec.	Contracts
✓ User needs	✓ electrical	✓ R&R
✓ Products	✓ Pneumatic	✓ certifications
✓ Prim. packaging	✓ Automation	✓ Document approval
✓ KPIs		✓ User
✓ Kits		✓ KPIs target
✓ validation		✓ Payment terms
✓ documentation		✓ Key milestones
✓ training		✓ KM
✓ maintenance		✓ Commissioning FAT SAT
 ✓ Spare part + ERES + Alarm ✓ Automation 		 ✓ Support mentoring



5










Integration into existing process

• Where does it fit in?



- Inline after Filling
- Standalone "island concept"
- Before labelling
- Or all in one line / feedback or bottlenecking ?
- How to maintain clean room conditions
- When integrated in existing line
 - How to connect the parts
 - Who will be responsible for this
 - What about AQL sampling: manual, automatic




Need to build a Business Process Mapping





Business Process Mapping










Need for SIPOC before Deep Dive into details







Integration into existing processes

- Online versus offline:
 - Inline after filling
 - More appropriate in case cold chain
 - But influenced by process circumstances before
 - Offline
 - Independent of the process circumstances before
 - But more labor
 - More handling, more risks, e.g. Mix-ups



Product behavior

- Viscous. If so the introduction of air bubbles is likely
- Humans can distinct air bubbles from particles far better
- Offline would be more appropriate





Integration into existing process

Product behavior

- If your products are a mix of waterlike to viscous
- Make it two ways. Partly inline, partly offline





AVI in general

- These machines are complex
- They may go in error
- you might be confronted with unexpected high ejects
- Buffering and offline inspection should be considered




Some Prerequisites

Representative test kits are prepared

- Defect units (defined and stable)
- Worst case
 - Product and/or container
- Good units





MVI results on these test kits are known

- Statistical results, e.g. through Knapp Kushner
- Human limits
 - Particle size
 - Areas not easy to inspect







Considerations when Selecting

There are only few mayor machine suppliers Your URS and engineering specs are the basis

• The machine supplier must meet these requirements / time /Cost



GOOD GREAT

AVI must perform equal or better than MVI

• How much better

The statistical result on these test kits must be equal or better than MVI

- Against what costs
- Is manual inspection of AVI ejects allowed
- AVI is not perfect
- 100% detection of everything not wanted is impossible





Total Cost ?



The Price? **GOOD QUESTION!**

Apart from wanted performance, machine price only

- Printers are sold at/or below cost price
 - They earn in selling ink
- What about spare parts
 - What do you minimal need
 - Life cycle?
 - Costs?
 - Total Cost of Ownership
 - Ressources on project to secure planning

Mechanical you can get everything

- OEM (Original Equipment Manufacturer)
- Third parties
- Unlimited in time







Considerations when Selecting

Electrically

- Lifecycle is short
- Ongoing development is rapid
- Older parts become obsolete in short time
- Availability is limited in time



- Machine suppliers often don't produce these parts, they buy on the market
- Certification by geographic area Eur / US / Can / JP





Cameras/LEDs

Innovation vs long term solutions

Machine supplier guaranties

- Spare parts are available for 10 ? 15 years?
- Equal with LEDs and cameras?





Supplier decision matrix

□ Technical & Engineering Design

Performance

Automation

Quality

EHS Process Safety

□ Commercial - Support





Why a Business Process Mapping ?






18

© Copyright GSK for internal use only Author Romain Veillon



Mapping of information flow

Focus VI entire Process not only AVI equipment








© Copyright GSK for internal use only Author Romain Veillon



SCIENCE*

Business Process Mapping

• And move forward to elaborate a fully transparent flow of information inside AVI







Still a V Model ? => No






© Copyright GSK for internal use only Author Romain Veillon



Qualification Path with QbD



Key learning: GSK new validation framework puts strong effort on initial RA and DQ IQ OQ test must only mitigate risk identified during RA no additional test must be done if not critical

IQ OQ test may be driven by RA and GMP UR





Why Risk Assessment is key?







23



Process System Risk Assessment

- 1. Divide the process is sub process steps
 - ✓ Pre requisite
 - ✓ Warehousing
 - ✓ Handling unit Deconditioning

✓ AVI _____

- ✓ Leak Testing (if any)
- ✓ AVI control strategy
- ✓ Handling unit reconditioning
- ✓ 2 nd stage (if any)
- ✓ MVI Control Strategy (AQL+trend chart)
- \checkmark End of operations

Unit presentation to camera by mechanical handling Unit presentation to camera with product rotation Unit presentation to camera with glass & product dependent parameters Refeed transport mode Lightning to camera Image acquisition Digital Image Processing Result transfer to shift register Physical unit ejection Inspection result archiving (SQL) Functional test kit, after operations Batch closure and local report creation Central reporting & archiving





Risk Assessment

Identify CQA CPP and Critical Design Elements

\checkmark Some CQAs for VI

Atributes							
CQA	A CQA		CQA	CQA	CQA	PA	
Identity	Essentialy free of glass Defect/Particles/Stopper defect/Closure defec. fill level/Empty/Lyo defect	Leak absence	Container Integrity	Stength, Potency	Potency (sheer stress)	Equipment Performance	

- \checkmark If at least 1 CQA is impacted the parameters becomes a CPP
- ✓ Data criticality has to be evaluated, Critical design element explored with supplier + list of alarms





Risk Assessment


Identify the risk (unwanted event / cause / consequence) Example

Phase 1 : Process Analysis				Phase 2 : Risk Identification & Evaluation			
	Process Step			Unwanted events			
		Process Sub- Step/Description	Parameter or critical aspect	Unwanted event description	Because of	With the consequences	
	1 Prerequisite	Set up AVI recipe loading	Recipe name and versioning choice for all sub-config (motion, light, handling, image processing), and product	Wrong selection of recipe parameters	Previous recipe available for selection	Use of wrong parameters for lot inspection	





Risk Ass. can mitigate risks in multiples pathways : not only IQ OQ PQ





Risk Assessment: Risk control




	Phase 3: Risk Control Strategy							
	To draft during URS and finalize in DQ							
To avoid occurrence		To limit impact		To increase detectability				
Туре	Description	Туре	Description	Туре	Description	Justification / Comment	Critical Design Element / Function	
Design	In production mode only validated recipes can be loaded. Previous version of recipe are present but not visible to the operator in production mode. Copy of parameters from an old recipe using configuration mode is allowed on not validated product.	Other	Not applicable	other	Notapplicable		Only validated recipes can be loaded in production mode	







Design your qualification:



Installation Qualification

 Documentation verification, component data verification, drawings, system Installation verification, utilities, Software and IT verification

Operational Qualification

- HMI Layout verification
- Alarms verification
- Screen navigation, access verification, security verification
- ER/ES verification (electronic Records and signatures)
- MES (Manufacturing Execution System) server communication
- Backup / Restore and disaster recovery
- Containers handling
- Counters and cells control
- VI critical parameter control (baseline)
- Recipes version verification
 -not exhaustive list





FAT

- Should not be on user site
- Use supplier facilities / competencies
- If not passed
 - Due to minor issues
 - Due to mayor issues
- Never expect it will be solved during SAT
- \Rightarrow Punch list is key at supplier site
- ⇒ All key ressources are at supplier site Do not postpone





You have learnt

- UR vs eng spec vs procurement contracts
- URS content
- URS for Deep Learning Infra
- Business process Mapping IPO
- Risk assessment by block Fx
- Procedural ctrl
- Mitigation in Validation / SOP / maint
- Design Qualification plan
- FAT / SAT

- Design qualification is not qualification?
- Risk assessment is foundation of validation plan?
- URS should encompass CSV for AVI ?
- URS content is all GMP?
- Contractual requirement are not all GMPs?
- At the end of validation PQ all risks are mitigated ?
- Business process mapping will help to write URS and risk assessment ?
- AVI is just a part of overall VI process